



APPROVALS

AS 2419.1
 Feed & tee: Rilsan coated AS 4020
 Pipe: AS 1074 Hot Dipped Gal
 Booster: AS 2419.3 (Approved)
 SDCV: UL/FM listed (Approved)
 Hydrant valve: AS 2419.2
 Butterfly valve: UL/FM listed (Approved)
 Couplings: UL/FM listed

INSTALLATION

Connect to service 100mm above finished ground level with copper x roll groove adaptors or flanges (either supplied)

BRIGADE CONNECTIONS

All Australian fire authorities available

OPTIONS AVAILABLE

By-pass / meter to suit local water authority requirements
 Butterfly valve installed under booster head where head pressure is greater than 50 kPa

WORKING PRESSURE

Couplings: 2068 kPa
 Booster: 1400 kPa
 SDCV: 1200 kPa
 Hydrant valve: 1850 kPa
 Butterfly valve: 1600 kPa

Sizes may vary due to supply of product, contact office to confirm

