



### APPROVALS

AS 2419.1  
 Feed & tee: Rilsan coated AS 4020  
 Pipe: AS 1074 Hot Dipped Gal  
 Booster: AS 2419.3 (Approved)  
 SDCV: UL/FM listed (Approved)  
 Hydrant valve: AS 2419.2  
 Butterfly valve: UL/FM listed (Approved)  
 Couplings: UL/FM listed

### INSTALLATION

Connect to service 100mm above finished ground level with copper x roll groove adaptors or flanges (either supplied)

### BRIGADE CONNECTIONS

All Australian fire authorities available

### OPTIONS AVAILABLE

By-pass / meter to suit local water authority requirements  
 Butterfly valve installed under booster head where head pressure is greater than 50 kPa

### WORKING PRESSURE

Couplings: 2068 kPa  
 Booster: 1400 kPa  
 SDCV: 1200 kPa  
 Hydrant valve: 1850 kPa  
 Butterfly valve: 1600 kPa

\*Sizes may vary due to supply of product, contact office to confirm\*

